

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. <del>S.</del> R. <u>34</u> <del>E.</del> W.	<u>G5</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on August 9, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Wood post	(Not found. See B, below, for subsequent monuments.)
Spruce 6 S56W 07	(Not found. No subsequent accessories found.)
Fir 10 N23E 12	(Not found. No subsequent accessories found.)

B. In 1854, the subdivision work of this township was examined by A. B. Woods, Deputy Surveyor, to check on the 1851 work quality. He commented that some of the corners did not appear to have been corrected from the random lines. The undersigned believes this to be one such corner. Corners 1/2 and 1 mile N are confirmed originals, but when a line is extrapolated southward from them the record distance, lines to E and W across the S lines of Sec. 9 & 10 do not come even close to agreeing with the original calls to major streams to E & W, although the actual distance between these rivers does agree very closely with the record. Therefore, the departure of this corner was determined from the rivers, while the latitude was made proportional to the record distance between an M.C. to S and an original 1/4 cor. to N. Found a flat iron bar, with a squared post next to it, N72°E 61.5 ft. (also, a Northern Paper Mills L. P. on a nearby hemlock stub); and a 3"x3"x5' squared post N58°E 30.5 ft., both intended to represent this corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1" I.D. x 36" iron pipe with 4" aluminum cap.  
 Red Maple 13 N65°W (mag.) 13.0 ft. "S9, NBT"  
 Red Maple 16 N33°E (mag.) 29.2 ft. "S10, NBT"  
 Sugar Maple 8 S71°E (mag.) 14.1 ft. "S15, NBT"  
 Variation at this corner is 0°55' West

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE May 22, 1976  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

