

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 ^{N.} 34 R. 34 ^{W.} 34	G6
2. PROPERTY CONTROLLING IN SECTION	16, T. 45 ^{N.} 34 R. 34 ^{W.} 34	7a & 7b
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ ^{N.} _____ R. _____ ^{E.} _____ ^{W.} _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G6: Wood post (Not found. No subsequent monuments found.)
 Fir 6 S57W 16 (Not found. No subsequent accessories found.)
 Fir 8 N69E 34 (Not found. No subsequent accessories found.)
 Corners 7a & 7b: These were meander corners established on the section line between 15 & 16, on the N and S banks of Net River respectively. No evidence of original posts or their accessories or of any replacement monuments or accessories, was found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G6: Re-established 7/29/74 proportionately on line between North M.C. bet. 15 & 16 6.227 ch. N and Sec. Cor. 39.948 ch. S.
 Corner 7a: Re-established 9/18/72 on N. bank of Net River by reference to original meander notes. Owing to the peculiar lay of the land at this point, it is possible to pinpoint with all probability of being essentially correct, the original M.C. position. For precedent in using this procedure, see N. Sperhake's corner record for the re-establishment of Sec. Cor. 15, 16, 21, & 22, on file in Iron Co. Register of Deeds Office.
 Corner 7b: Re-established 7/29/74 proportionately on line between North M.C. bet. 15 & 16 1.021 ch. N and 1/4 cor. 5.206 ch. S. Found this position to be very consistent with original field

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 [notes for both section line and meander line.]

Corner G6: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 White Birch 5 North (mag.) 15.3 ft. "1/4S, NBT"
 White Spruce 6 S66°E (mag.) 5.2 ft. "1/4S, NBT"
 Corner 7a: 1" I.D. x 36" iron pipe with 4" aluminum cap.
 Cedar 20 S85°E (mag.) 15.7 ft. "M.C., NBT"
 Cedar 15 S80°W (mag.) 30.2 ft. "M.C., NBT"
 Also squared and scribed a 10" W. Spruce S19°W 2.6 ft.
 Corner 7b: 1" I.D. x 36" iron pipe with 3½" aluminum cap.
 B. Ash 7 S37°E (mag.) 35.5 ft. "M.C., NBT"
 Elm 7 N78°E (mag.) 52.2 ft. "M.C., NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE May 24, 1975
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

