

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> ^{N.} XXX , R. <u>34</u> ^{XXX} W.	<u>E7</u>
2. PROPERTY CONTROLLING IN SECTION <u>16</u>	T. <u>45</u> ^{N.} XXX , R. <u>34</u> ^{XXX} W.	<u>15 & 15a</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S., R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner E7: Wood post** (Not found. See B, below, for subsequent monuments.)
- Tamarack 10 N19E 11 (Not found. No subsequent accessories found.)
- Tamarack 12 S61W 14 (Not found. No subsequent accessories found.)
- Corner 15: Not established in original survey nor subsequently, apparently.**
- Corner 15a: Wood post** (Not found. No subsequent monuments found.)
- Spruce 12 N50W 58 (Not found. No subsequent accessories found.)
- Elm 12 S45W 79 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner E7: Re-established 8/21/72 by double proportionate measurement from corners 3 miles S, 2 miles N, 3 miles E and 2 miles W. Distances to stream W and N check well with original notes. Found a down, squared spruce post N7°W 61.4 ft. with Northern Paper Mills L. P. on nearby tree. L. P. bears legend "ABOUT SEC. COR."**
- Corner 15: Established 7/31/74 proportionately on line between Sec. Cor. 19.996 ch. W and Sec. Cor. 59.986 ch. E.**
- Corner 15a: Re-established 7/31/74 on W. bank of Net River on true section line, 44.007 ch. W of Sec. Cor. 15, 16, 21, & 22 and 35.975 ch. E. of Sec. Cor. 16, 17, 20 & 21. Set inshore for protection from spring run-off high water. 1/4 cor. is in river 4.016 ch. E.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner E7: 1" I.D. x 32" iron pipe with 4" aluminum cap.**
- Tamarack 6 N22°W (mag.) 30.6 ft. "S17, NBT"
- Tamarack 6 S65°W (mag.) 21.2 ft. "S20, NBT"
- B. Spruce 7 S34°E (mag.) 25.5 ft. "S21, NBT"
- Corner 15: 1" I.D. x 36" iron pipe with 3½" aluminum cap.**
- Red Maple 5 N16°W (mag.) 12.1 ft. "1/16S, BT"
- Red Maple 4 S50°W (mag.) 11.0 ft. "1/16S, BT"
- Corner 15a: 1" I.D. x 36" iron pipe with 3½" aluminum cap.**
- B. Ash 16 N23 E (mag.) 18.6 ft. "M.C., NBT"
- Elm 42 S13°W (mag.) 39.5 ft. "M.C., NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE May 22 1975

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

