

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|---|--|-------------------------|
| 1. PUBLIC LAND SURVEY_____ T. _____ | N. _____ E. _____ S., R. _____ W. _____ | _____ |
| 2. PROPERTY CONTROLLING IN SECTION <u>16</u> , T. <u>45</u> | N. _____ E. _____ S., R. <u>34</u> 34 W. _____ | <u>14, 16 & 16a</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ | N. _____ E. _____ S., R. _____ W. _____ | _____ |
| 4. LOT NO. _____ , RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on July 29 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corners 14 & 16: Not established in original survey nor subsequently, apparently.
 Corner 16a: Wood post (Not found. No subsequent monuments found.)
 Cedar 16 N50E 30 (Not found. No subsequent accessories found.)
 Fir 12 S65W 46 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 14: Established on line between Sec. Cor. 19.974 ch. S and 1/4 cor. 19.974 ch. N. Found a 3"x3"x4' squared post S17°W 41.7 ft. for an approximate corner. Corner falls on edge of swamp SW & NE.
 Corner 16: Established proportionately on line between Sec. Cor. 19.996 ch. E and 59.986 ch. W. (No 1/4 cor. ever established on this line.)
 Corner 16a: Re-established on E. bank of Net River on true section line, 38.161 ch. W. of Sec. Cor. 15, 16, 21 & 22 and 41.821 ch. E of Sec. Cor. 16, 17, 20, & 21. This corner is not at proportionate position, but was moved inshore for protection from spring run-off highwater. 1/4 cor. is in river 1.830 ch. W. of this monument. Position agrees substantially with original

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

)meander line notes.

Monuments for all three corners: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
 Witnesses for Corner 14: Cedar 10 N 4°E (mag.) 36.3 ft. "1/16S, BT"
 W. Birch 6 S87°E (mag.) 22.9 ft. "1/16S, BT"
 Witnesses for Corner 16: W. Spruce 11 N80°E (mag.) 14.1 ft. "1/16S, BT"
 Sugar Maple 6 N 2°E (mag.) 18.1 ft. "1/16S, BT"
 Witnesses for Corner 16a: W. Birch 16 S50°E (mag.) 9.9 ft. "M.C.,NBT"
 B. Ash 7 N11°E (mag.) 19.7 ft. "M.C.,NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE May 22, 1975
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

