

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>20</u>	T. <u>45</u> N. <u>34</u> E. S., R. _____ W.	14b & 14c
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 26 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner 14b: Wood post
Willow 7 South 18
W. Birch 7 S15W 76

Corner 14c: Wood post
W. Birch 10 N15W 42
W. Birch 8 N12E 60

No original monuments or accessories, nor any replacement monuments or accessories, found at either corner.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner 14b: Re-established on true section line on S. bank of a wide area of Net River, 18,887 ch. N of Sec. Cor. 20, 21, 28, & 29 and 21.113 ch. S of 1/4 cor. bet Sec. 20 & 21, about 10 ft. from water's edge. Set inshore for protection from spring run-off high water. This is the middle one of three M.C.'s established on this line.

Corner 14c: Re-established on true section line on N. bank of a wide area of Net River, 10,066 ch. N of Sec. Cor. 20, 21, 28, & 29 and 29.934 ch. S of 1/4 cor. bet. Sec. 20 & 21, about 10 ft. in from water's edge. Set inshore for protection from spring run-off high water. This is the south one of three M.C.'s established on this line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for both corners: 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.

Witnesses for Corner 14b: No suitable trees near, therefore, no witnesses.

Witnesses for Corner 14c: Cedar 17 N48°W (mag.) 26.1 ft. "M.C., NBT"
B.Ash 5 N44°E (mag.) 19.4 ft. "M.C., NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

