

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. XXX , R. <u>34</u> XXX W.	<u>A9; A10; & A11</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- Corner A 9: Fir post Not found. Found L.E.S. post N88°W 59 lks.
 - Cedar 12 S52E 11 (
 - Hemlock 18 N84W 19 (Not found. No subsequent accessories found.
 - Cedar 6 S71W 16 (
 - Fir 6 N73E 26 (
 - Corner A10: Tamarack post Not found. Found L.E.S. post N82°W 117 lks.
 - Spruce 5 S67E 15 (
 - Tamarack 5 S38W 14 (Not found. No subsequent accessories found.
 - Corner All: Spruce post Not found. Found L.E.S. post N42°W 79 lks.
 - Spruce 6 N33E 52 (
 - Spruce 6 S65E 65 (
 - Tamarack 12 S18W 15 (Not found. No subsequent accessories found.
 - Tamarack 6 N68W 50 (
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- Corner A 9: Re-established 8/18/72 on line between twp. corner 159.896 ch. S and original section corner 159.896 ch. N.
 - Corner A10: Re-established 8/23/72 on line between twp. corner 119.922 ch. S and original section corner 199.870 ch. N.
 - Corner All: Re-established 8/23/72 on line between twp corner 79.948 ch. S and original section corner 239.844 ch. N. Distances to swamp edges 2.00 ch. S and 3.00 ch. N check as well as one can tell by the indefinite edges.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.
 - Witnesses for Corner A9: W. Pine 9 N88°W (mag.) 17.7 ft. "S24, NBT" (Variation 3°30' West) W. Pine 8 N23°E (mag.) 25.4 ft. "S19, NBT" W. Spruce 7 S83°E (mag.) 20.7 ft. "S30, NBT"
 - Witnesses for Corner A10: Tamarack 3 N59°E (mag.) 67.0 ft. "1/4S, NBT" Tamarack 6 N 8°W (mag.) 83.3 ft. "1/4S, NBT"
 - Witnesses for Corner All: B. Spruce 6 N67°W (mag.) 43.4 ft. "S25, NBT" (Variation 0°00') R. Maple 5 S23°W (mag.) 68.7 ft. "S36, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE December 28, 1973

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

