

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. <u>34</u> <del>33</del> R. <u>34</u> <del>33</del> W.	C13 and D13
2. PROPERTY CONTROLLING IN SECTION <u>32</u>	T. <u>45</u> N. <u>34</u> <del>33</del> R. <u>34</u> <del>33</del> W.	16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 15 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- Corner C13:** Spruce post Not found. Found squared stake N78°W 51.8 ft.  
 Spruce 7 N56E 35 )  
 W. Pine 16 N8½W 78 ) Not found. No subsequent accessories found.
  - Corner D13:** Sugar post Not found. No subsequent monuments found.  
 Y. Birch 28 N60½W 48 )  
 Sugar 7 N37½E 19 ) Not found. No subsequent accessories found.
  - Corner 16:** Not established in original survey nor subsequently, apparently.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- Corner C13:** Re-established proportionately on line between original section corner 160.104 ch. E and twp. corner 79.052 ch. W.
  - Corner D13:** Re-established proportionately on line between original section corner 120.078 ch. E and twp. corner 119.078 ch. W.
  - Corner 16:** Established on line between 1/4 corner 20.013 ch. W and section corner 20.013 ch. E.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- Monuments for all three corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.
- Witnesses for Corner C13:** Tamarack 11 S81½°W (mag.) 44.5 ft. "S6, NBT"  
 R. Pine 20 N45°W (mag.) 95.5 ft. "S31, NBT"
- Witnesses for Corner D13:** Red Maple 11 N14°W (mag.) 4.4 ft. "1/4S, NBT"  
 Red Maple 11 S83°E (mag.) 28.5 ft. "1/4S, NBT"
- Witnesses for Corner 16:** Hemlock 22 S77°E (mag.) 13.5 ft. "1/16S, BT"  
 Red Maple 6 S30°W (mag.) 12.4 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE December 28, 1973

MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

