

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> <sup>N.</sup> <del>XX</del> , R. <u>34</u> <sup>XX</sup> <del>W.</del>	<u>A7; A8; &amp; B7</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____, S. _____, R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, S. _____, R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

None of the original posts or accessories for these corners was found. Corner A7 had been marked approximately with an L.E.S. control post N12°E 1.64 ch. and another wood post S60°E .46 ch. set by unknown parties. Corner A8 had been marked approximately with an L.E.S. control post S50°E .39 ch. No subsequent monuments found at Corner B7.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner A7: Re-established 8/18/72 on line between twp. corner 239.844 ch. S and an original section corner 79.948 ch. N. Note: There is a U.S.F.S. monument at Corner A6, purporting to be set from an original BT. The undersigned questions the identification of the evidence; therefore, the U.S.F.S. corner, which bears N0°16'E 40.16 ch. from Corner A7, was not used for proportioning.  
 Corner A8: Re-established 8/18/72 on line between twp. corner 199.870 ch. S and original section corner 119.922 ch. N.  
 Corner B7: Re-established 11/19/73 proportionately on line between section corners 40.073 ch. E and 39.163 ch. W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Monuments for all three corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.  
 Witnesses for Corner A7: Sugar Maple 8 N66°E (mag.) 10.5 ft. "S18, NBT"  
                                     Sugar Maple 6 N89°W (mag.) 13.9 ft. "S13, NBT"  
                                     Red Maple 8 S75°E (mag.) 9.0 ft. "S19, NBT"  
 Also squared & scribed a 14" red maple N30°W 3.1 ft. from corner.  
 Witnesses for Corner A8: Sugar Maple 6 S17°W (mag.) 9.6 ft. "1/4S, NBT"  
                                     Sugar Maple 9 N19°E (mag.) 17.4 ft. "1/4S, NBT"  
 Also squared & scribed a 4" ironwood S18°W 3.3 ft. from corner.  
 Witnesses for Corner B7: Red Maple 10 S41½°W (mag.) 13.6 ft. "1/4S, NBT"  
                                     Red Maple 9 N56°W (mag.) 19.9 ft. "1/4S, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE December 28, 1973  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581