

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. XX R. <u>34</u> XX W.	<u>D5; E5; & E6</u>
2. PROPERTY CONTROLLING IN SECTION <u>16</u>	T. <u>45</u> N. XX R. <u>34</u> XX W.	<u>3</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corners D5, E5, and E6: Original posts or accessories not found. D5 marked approximately by a dead 12" hemlock squared on four sides, with Northern Paper Mills location poster marked "About 1/4 cor." attached. E5 marked approximately by Northern Paper Mills foresters with a 2"x2"x3' squared post N30°E 1.00 ch. from corner. At E6, nothing found.

Corner 3: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner D5: Re-established 11/19/73 on line between section corners 39.653 ch. to E and W. Note: This section line is 1.50 ch. shorter than record distance; blunder probably occurred at one place in original survey, but there is no way of telling where, thus corner re-established at midpoint.
Corner E5: Re-established 11/10/72 by double proportionate measurement from corners 1 mile N, 1 mile S, 1 mile W, and 2 miles E.
Corner E6: Re-established 11/14/72 on line between section corners 39.959 ch. to N and to S.
Corner 3: Established 11/17/72 on line between sec. corner 19.979 ch. N and 1/4 corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

19.979 ch. S.

Monuments for all four corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.
Witnesses for Corner D5: Sugar Maple 6 S 1°W (mag.) 14.4 ft. "1/4S, NBT"
 Sugar Maple 9 N72°E (mag.) 37.2 ft. "1/4S, NBT"
Witnesses for Corner E5: Sugar Maple 6 N66°E (mag.) 30.0 ft. "S9, NBT"
 (Variation 1°25' West) Sugar Maple 8 N36°W (mag.) 5.2 ft. "S8, NBT"
 Sugar Maple 10 S12°W (mag.) 10.6 ft. "S17, NBT"
Witnesses for Corner E6: Red Maple 11 N35½°W (mag.) 20.5 ft. "1/4S, NBT"
 Cedar 22 N61°E (mag.) 37.8 ft. "1/4S, NBT"
Witnesses for Corner 3: Sugar Maple 12 S37½°W (mag.) 35.0 ft. "1/16S, NBT"
 Sugar Maple 5 S75°E (mag.) 8.6 ft. "1/16S, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE December 28, 1973

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

