

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> XX N. R. <u>34</u> XX W.	E10; E11; and F11
2. PROPERTY CONTROLLING IN SECTION <u>29</u>	T. <u>45</u> XX N. R. <u>34</u> XX W.	14
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Found no evidence of original posts or their accessories at any of these corners. At E10, found a dead 10" aspen blazed on 4 sides for an approximate corner S73°W .505 ch.; at E11, found a forester's picket for an approximate corner N53°E .78 ch.; at F11, found a 3"x3"x4' squared cedar post N41°E 32.8 ft., for an approx. corner.

Corner 14: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E10: Re-established 9/7/72 on line between section corners 40.55 ch. to N and to S.

Corner E11: Re-established 8/3/72 by double proportionate measurement between corners 1 mile E, 2 miles W, 2 miles N, and 1 mile S.

Corner F11: Re-established 8/20/73 on line between section corners 40.253 ch. to E and to W.

Corner 14: Established 9/8/72 on line between section corner 20.277 ch. S and 1/4 corner 20.278 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monuments for E10, E11, & F11: 1" I.D. x 36" iron pipe with 4" aluminum cap.

Witnesses for Corner E10: Sugar Maple 8 S33°W (mag.) 16.2 ft. "1/4S, NBT"
W. Spruce 5 S72½°E (mag.) 9.1 ft. "1/4S, NBT"

Also squared & scribed a 4" balsam N58½°W 1.8 ft. from corner.

Witnesses for Corner E11: W. Birch 10 N26°E (mag.) 16.7 ft. "S29, NBT"
Sugar Maple 6 S12°E (mag.) 15.4 ft. "S33, NBT"

Witnesses for Corner F11: Sugar Maple 6 N78°E (mag.) 19.0 ft. "1/4S, NBT"
Sugar Maple 6 S20½°E (mag.) 9.8 ft. "1/4S, NBT"

Corner 14: 1" I.D. x 36" iron pipe (no cap); Pipe angled - top is on the corner point
Cedar 10 S60°W (mag.) 25.7 ft. "1/16S, BT"
Cedar 10 N31°W (mag.) 21.1 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE January 31, 1974

Arthur O. Enger
MICHIGAN REGISTERED LAND SURVEYOR
Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

