

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> N. XX R. <u>34</u> XX W.	E9
2. PROPERTY CONTROLLING IN SECTION <u>29</u>	T. <u>45</u> N. XX R. <u>34</u> XX W.	7; 7a; and 7b
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E9, 7a, and 7b: None of the original posts or accessories were identified. At E9, found what may have been the point of a rotted off post N25½°W .583 ch., but if it was, it was probably placed there by Northern Paper Mills foresters in the early 1950's for an approximate corner. Found no subsequent monuments at Corners 7a and 7b. Note: 7a and 7b are the meander corners on the Net River; Corner E9 is indicated in the original field notes as also being a meander corner, as well as a section corner.
Corner 7: Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E9: Established 9/5/72 on shore of Net River 80.00 ch. S of Sec. Cor. 16, 17, 20, & 21, as found by A. B. Woods, Deputy Surveyor, in an 1854 examination of the 1851 subdivision survey, which reported the distance to be 80.56 ch. The 80.00 ch. distance more nearly fits the observable conditions on the ground, bearing in mind that this corner was also a meander corner.
Corner 7: Established 9/7/72 on line between sec. corner 20.277 ch. N and 1/4 corner 20.277 ch. S.
Corner 7a: North M.C. re-established 9/5/72 proportionately on line between section corners 9.827 ch. N and 71.284 ch. S. Corner falls about 10 ft. N. of edge of river, in a place likely to have been used in the original survey.
Corner 7b: South M.C. re-established 9/7/72 on line between section corners 13.230 ch. N and 67.692 ch. S. This is not proportional to original distance, which falls in the river about 19 links N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(River high when monument set.)

Monuments for all four corners: 1" I.D. x 36" iron pipe with 4" aluminum cap.
Witnesses for Corner E9: Red Pine 8 N76°W (mag.) 30.1 ft. "S20, NBT"
 (Variation 1°00' West) W. Pine 20 S36°W (mag.) 20.0 ft. "NBT"
Witnesses for Corner 7: Sugar Maple 14 S21°E (mag.) 4.4 ft. "1/16S, BT"
 Red Maple 5 N57½°W (mag.) 20.8 ft. "1/16S, BT"
Witnesses for Corner 7a: B. Ash 12 N9½°E (mag.) 15.0 ft. "MC, NBT"
 B. Ash 8 N39°W (mag.) 1.9 ft. "MC, NBT"
 Also squared and scribed a 5" B. Ash S66°E 3.0 ft. from corner.
Witnesses for Corner 7b: Cedar 14 S60°E (mag.) 33.5 ft. "MC, BT"
 Cedar 7 N48°E (mag.) 33.6 ft. "MC, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 31, 1974

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

