

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>45</u> <sup>N.</sup> <del>XX</del> R. <u>34</u> <sup>XX</sup> <del>W.</del>	<u>C6; C7; and D7</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on see below 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Found no evidence of original posts or accessories at any of these corners, nor any replacement monuments or accessories except at Corner C7, where an approximate corner post has been set by unknown parties N10°E 1.65 ch. from corner reported here; and at Corner D7, where a 9" maple had been blazed for an approximate corner N14°E .33 ch. from corner.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner C6:** Re-established 11/17/72 on line between section corners 40.053 ch. to N and to S.
- Corner C7:** Re-established 8/21/72 by double proportionate measurement from corners 3 miles S, 2 miles N, 1 mile W, and 4 miles E.
- Corner D7:** Re-established 11/10/72 on line between section corners 40.080 ch. to E and to W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Monuments for all three corners:** 1" I.D. x 36" iron pipe with 4" aluminum cap.

**Witnesses for Corner C6:** W. Spruce 16 S22°W (mag.) 31.5 ft. "1/4S, NBT"  
 W. Spruce 11 S76°E (mag.) 30.5 ft. "1/4S, NBT"  
 R. Maple 6 N11°E (mag.) 26.8 ft. "1/4S, NBT"

**Witnesses for Corner C7:** W. Pine 11 N30°E (mag.) 31.9 ft. "S17, NBT"  
 Aspen 11 S25°E (mag.) 29.5 ft. "S20, NBT"

Also squared & scribed a 12" aspen N76°E 4.0 ft. from corner. Monument set in a pile of rocks.

**Witnesses for Corner D7:** Red Maple 14 S16°W (mag.) 5.3 ft. "1/4S, NBT"  
 Sugar Maple 8 N75°W (mag.) 13.7 ft. "1/4S, NBT"  
 Sugar Maple 8 N16°E (mag.) 12.5 ft. "1/4S, NBT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE January 031, 1974  
MICHIGAN REGISTERED LAND SURVEYOR

**Arthur O. Enger**  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

