



SURVEY & REMONUMENTATION

Stock No. 26273

MAR 19 1997

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

Iron
(County)

Located In:

Corner Code #

1. Public Land Survey

T 46N R 34W

C-13

~~T 46N R 34W~~

~~C-1~~

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

IRON COUNTY
MICHIGAN
RECEIVED FOR RECORD
96 DEC 23 AM 9:01
L.C. Records L.7, P.40
Gilbert [Signature]
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 31 & 32, T46N R34W,
6 & 5, T45N R34W,

I, Gary L. Pisoni, in a field survey on October 22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt, U.S. Deputy Surveyor on September 18, 1846.

Original corner: Fir Post
Original bearing trees:

Fir	9"	N 40° E	37 Links (24.42 feet)
Yellow Birch	12"	N 73° W	27 Links (17.82 feet)

Original Subdivision established by Guy H. Carleton on July 26, 1851.

Original bearing trees:

Yellow Birch	10"	S 60° W	23 Links (15.18 feet)
Fir	10"	S 15° E	16 Links (10.56 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found.

Found a wood post which was being used as the corner, but post was to far out of position to be accepted as the Section corner. G.L.O. distance along Town line is very close to the actual distance measured between other GLO corners East and West. I felt the best location for restoring the corner position would be to proportion the corner between the North Quarter corner of Section 6 and the North Quarter corner of Section 5, T45N R34W.

Corner Record Research on file with County Representative.

PEER GROUP APPROVED
By Deon Gary J. Pisoni 12-11-96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T46N, R34W, S-31, S-32, S-6, S-5, T45N, 1996, RLS-27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

White Spruce	12"	N 71° E	12.01 feet
White Spruce	11"	S 50° E	27.04 feet
White Spruce	11"	S 18° W	28.14 feet
Black Spruce	8"	N 77° W	16.36 feet
Steel Sign Post	6'	N 07° E	1.03 feet
Wood Post	5" x 5" x 36"	N 80° E	35.00 feet



#96-18
Signed by Gary L. Pisoni
Surveyor's Michigan License No. 27457

Date 12-10-96

L.7 P.40