

# SURVEY & REMONUMENTATION



Stock No. 26273

MAR 19 1997

## COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 34W	D-13
	<del>T 45N R 34W</del>	<del>D-1</del>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

IRON COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
96 DEC 23 AM 9:02  
L.C. Records L. 7, P. 41  
*Gary L. Pisoni*  
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Quarter Corner between S. 32, T46N R34W  
S. 5, T45N R34W

I, Gary L. Pisoni, in a field survey on October 22, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
Original corner established by William A. Burt, U.S. Deputy Surveyor on September 18, 1846.  
Original corner: Fir Post  
Original bearing trees:  
Yellow Birch 22" N 45° E 38 Links (25.08 feet)  
Yellow Birch 10" N 55° W 27 Links (17.82 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
No original corner evidence found.  
Found the remains of a 4" dia. by 2 foot long wood post marking the corner position. G.L.O. distance check good East and West along Town line to other GLO corners.  
I accept the wood post as the best available evidence for restoring the corner position.  
Corner Record Research on file with County Representative.

PEER GROUP APPROVED  
*Gary L. Pisoni 12-11-96*  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
At the corner position, I set a 2" diameter by 30" long split base aluminum pipe monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T46N, R34W, 1/4, S-32, S-5, T45N, 1996, RLS-27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)  
Red Maple 10" N 10° W 33.87 feet  
Sugar Maple 9" N 67° E 20.34 feet  
Sugar Maple 10" S 44° W 26.92 feet  
Sugar Maple 8" N 52° W 61.00 feet  
Steel Sign Post 6' N 22° W 0.88 feet



#96-19  
Signed by Gary L. Pisoni Date 12-10-96  
Surveyor's Michigan License No. 27457

L. 7 P. 41