

SURVEY & REMONUMENTATION

FORM NO. 985-A



Stock No. 26273

MAR 19 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron
(County)

Located In:

Corner Code #

1. Public Land Survey

T 45N R 34W

F-3

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Quarter Corner between Sections 4 & 9, T45N R34W

I, Gary L. Pisoni, in a field survey on October 19, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Guy H. Carleton, U.S. Deputy Surveyor on July 20, 1851.

Original corner: Wood Post

Original bearing trees:

Hemlock	18"	S 08° W	14 links (9.24 feet)
Fir	10"	N 74° W	33 links (21.78 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original corner evidence found.

Found a 3" x 3" x 30" wood post marking corner position. Bearing and Distance check very good East and West to Section corners.

Accepted wood post as the best available evidence for restoring the corner position.

Corner Record Research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position, I set a 3/4" outside diameter by 3feet long aluminum rod monument with a 3" cast aluminum cap, stamped to read: Iron County Remonumentation, T45N, R34W, 1/4, S-4, S-9, 1996, RLS-27457 from which I established the following new blazed and scribed bearing trees: (all measurements taken to a nail in side of tree)

Sugar Maple	11"	N 11° W	42.38 feet
White Spruce	7"	S 54° E	15.76 feet
Sugar Maple	11"	S 07° E	33.22 feet
Sugar Maple	13"	S 82° W	27.09 feet
Steel Sign Post	6'	S 41° W	0.79 feet

IRON COUNTY
RECEIVED FOR RECORD

96 DEC 23 AM 9:01

L.C. Records L.7, P.39


Gilbert J. Pisoni
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3						♦							
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

PEER GROUP APPROVED

Iron Gary L. Pisoni 12-11-96
COUNTY REPRESENTATIVE



#96-17
Signed by *Gary L. Pisoni* Date 12-10-96

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

L.7 P.39