

**SURVEY &
REMONUMENTATION**

FEB 21 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMENCING YEAR 2000
RECEIVED FOR RECORD
IRON COUNTY, MICHIGAN

For corners in

_____ Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>34W</u>	<u>A-11</u> ✓
	T <u>45N</u> R <u>35W</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

00 DEC -8 PM 1:00
L.C. Records 1.8, P. 240
Gary L. Pisoni
REGISTERED PROFESSIONAL SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner to Sections 25 and 36, T45N, R35W
Section Corner to Sections 30 and 31, T45N, R34W

I, Gary L. Pisoni, in a field survey on March 20, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on September 17, 1846 by William A. Burt, U.S. Deputy Surveyor.
Original Corner; Spruce Post
Original Bearing Trees:

Spruce	6"	N 33° E	52 links (34.32 feet)
Tamarack	12"	S 18° W	15 links (9.90 feet)

In August 1851, Guy H. Carleton, U.S. Deputy Surveyor established the following new bearing trees:

Tamarack	6"	N 68° W	50 links (33.00 feet)
Spruce	6"	S 65° E	65 links (42.90 feet)

On 8/23/72, Arthur O. Enger RLS DNR restored the section corner position by proportionate measurement and set a 1" diameter by 36" long iron pipe with a 4" aluminum cap stamped as follows: T45N, R35W, R34W, S-25, S-30, S-36, S-31, RLS 13581 and recorded in Liber 1, Page 273-274 of LC records.

1972 Bearing Trees:

Black Spruce	6"	N 67° W	43.4 feet
Red Maple	5"	S 23° W	68.7 feet

PEER GROUP APPROVED
Gary L. Pisoni 11-30-2000
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found

On 3/20/2000 found monument as described above and the following bearing trees:

Red Maple	8"	S 23° W	68.90 feet
Spruce	9"	N 70° W	42.47 feet

Found existing bearing tree established by the U.S.F.S.:

Red Maple	7"	S 63° W	71.00 feet
Steel sign post		N 35° W	1.25 feet

Monument is 12" above ground surface.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Black Spruce	3"	S 82° E	49.28 feet
Steel sign post		N 86° E	0.85 feet

00-008

Signed by Gary L. Pisoni

Date 11-13-2000

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS - JAN. 28, 1978
REVISED MAY, 1978
REVISED JAN, 1983
REVISED OCT, 1995

LIBER 8 PAGE 240

