

**SURVEY &
REMONUMENTATION**

FEB 21 2001

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Iron (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>34W</u>	<u>A-12</u> ✓
	T <u>45N</u> R <u>35W</u>	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

COMMENCING YEAR 2000
RECEIVED FOR RECORD
IRON COUNTY, MICHIGAN

00 DEC -8 PM 1:01

L.C. Records 12.8. P. 245

Gary L. Pisoni
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner to Section 36, T45N, R35W
Quarter Corner to Section 31, T45N, R34W

I, Gary L. Pisoni, in a field survey on April 3, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established on September 17, 1846 by William A. Burt, U.S. Deputy Surveyor.
Original Corner; Sugar Post
Original Bearing Trees:

Cedar	14"	S 73° E	10 links (6.60 feet)
Sugar	6"	N 31° W	16 links (10.56 feet)

On 8/17/72, Arthur O. Enger, RLS DNR restored the quarter corner position by proportionate measurement and set a 1" diameter by 36" long iron pipe with a 4" diameter aluminum cap stamped as follows: T45N, R35W, R34W, 1/4, S-36, S-31, RLS 13581, recorded in Liber 1, Page 271-272 of LC records.

1972 Bearing Trees

Red Maple	5"	N 38° E	20.9 feet
White Spruce	14"	S 25° W	3.4 feet

PEER GROUP APPROVED

Gary L. Pisoni 11-30-2000
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original B.T.s found.

On 4/3/2000 found the above described monument and the following bearing trees:

Red Maple	8"	N 40° E	20.94 feet
Spruce	17"	S 27° W	4.00 feet

Found existing bearing tree established by the U.S.F.S.:

Sugar Maple	6"	N 67° W	17.07 feet
Steel sign post		S 74° W	1.0 feet

Monument is 12" above ground surface.

Corner record research on file with County Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Blazed and scribed the following new bearing trees: (All measurements taken to a nail in side of tree)

Sugar Maple	9"	N 26° W	30.61 feet
Steel sign post		North	0.65 feet

00-013

Signed by Gary L. Pisoni

Date 11-13-2000

Surveyor's Michigan License No. 27457

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 24, 1975
2745 REVISED JAN. 1983
REVISED OCT. 1995

