

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>34W</u>	<u>E9</u>
	T <u>45N</u> R <u>34W</u>	<u>G7</u>
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

G7 Feb 19 2004
 E9 May 03 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (E9) Corner common to Sections 20-21-28-29. Reestablished in 1974 by A.O. Enger, RLS. Set 1" ID x36" iron pipe with 4" aluminum cap. Red Pine 8 N76W 30.1', W.Pine 20 S36W 20.0'.
 (G7) Section corner 15-16-21-22. 1965: Reestablished by Neal Sperhake RLS by proportionate measurement. Set 1" ID I.pipe with 4" alum. Kimberly-Clark Corp cap. Maple 4 N40E 26.5 links, Maple 6 N29W 60 links, Maple 24 S62W 55 links, Cherry 10 S35E 54 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (E9) Recovered the 1974 monument in good condition and at record bearing and distance from the 1974 witnesses, both recovered in good condition with upper and lower blazes overgrown. Left the monument in place, made two new witnesses, and set measuring nails in the 1974 NBTs as described below. The monument is 3.5' West of the water's edge of the Net River this date.
 (G7) Found and accepted the 1965 monument in good condition and at record bearing and distance from the three Maple NBTs, in good condition. The Cherry NBT was not recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (E9) Found 1" ID iron pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: | (G7) Found 1" I.pipe with 4" alum. K-C cap. Blazed, scribed, and set measuring nails in: |
| 10" Spruce S19E 10.1' "S28 NBT" | 7" Spruce S43E 29.70' "S22 NBT" |
| 5" Spruce N33W 25.8' "S20 NBT" | Set nails and tags in the 1965 NBTs: |
| The 1974 witnesses: | 11" Maple N42E 17.45' old blazes |
| 20" W.Pine S38W 20.6' old blazes | 10" Maple N26W 39.70' do |
| 11" R.Pine N70W 32.2' (slope) do | 23" Maple S68W 36.35' do |
| Bearings are magnetic. Distances are to nail with tag. Set sq'd cedar post adjacent. | Set sq'd balsam post adjacent. Bearings are magnetic. Distances are to nail with tag. |



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 5/19/04