

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45NR</u> <u>34W</u>	<u>69</u>
	T <u> </u> <u> </u>	<u> </u>
	T <u> </u> <u> </u>	<u> </u>
	S <u> </u> <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>21</u> T <u>45NR</u> <u>34W</u>	<u>16</u>
	S <u> </u> <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> <u> </u>	<u> </u>
	S <u> </u> <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Feb 17 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G9) Corner common to Sections 21-22-28-27. 1965: Established by Neal Sperhake, RLS by proportionate measurement. Set 1"ID I.pipe with aluminum Kimberly-Clark Corp. cap. Tamarack 4 S58E 75 links, Tamarack 4 N33W 44 links, Tamarack 5 S17W 74 links.
 (16-Sec. 21) East 1/16 corner between Sections 21 and 28. 1974: Established by A.O.Enger RLS midway and on line between 1/4 corner West and Section corner East. Set 1"IDx36" I.pipe with 3.5" aluminum cap. Y.Birch 14 N12E 15.3', W.Birch 11 S46W 24.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G9) Found and accepted the 1965 monument, in good condition, and at record bearing and distance from the 1965 NBTs, recovered as follows: The Tamarack N'ly is dead and down; the Tamaracks SE and SW are standing with scribing visible, but are dead. This corner falls in an open swamp. Nearby trees are very small and most are dead. There are no suitable trees for NBTs nearby.
 (16-Sec. 21) Found and accepted the 1974 monument in good condition, in accord with the record, and at record bearing and distance from the 1974 BTs recovered as follows: The Y.Birch NE is in good condition, the W.Birch SW is a dead stub.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G9) Found 1"ID I.pipe with aluminum cap. Painted the 2 standing 1965 NBTs and set a sq'd cedar post 0.8' north of the corner monument. No suitable trees for new witnesses are nearby.	(16) Found 1"ID I.pipe with alum. MDNR cap. Blazed, scribed, and set measuring nails in: 14" Y.Birch N16E 16.0' "1/16S BT" * 15" Sugar S71E 37.2' do 16" Y.Birch S04E 18.1' do 14" Sugar N56W 10.0' do Bearings are magnetic. Distances are to nail with tag. Set Sq'd cedar post adjacent. * denotes the 1974 BT
---	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 5/19/04