

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>34W</u>	<u>F8</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>16</u>	_____
	T <u>45N</u> R <u>34W</u>	<u>4</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

F8 May 04 2004
 4 May 03 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (F8) Center of Section 21. Not established in the original survey.
- (4-Sec. 16) Northwest 1/16 corner, Section 16. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (F8) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.
- (4-Sec. 16) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (F8) Set 1" IDx32" I. pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: | (4) Set 1" IDx32" I. pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: |
| 12" Maple N27E 34.5' "C1/4 8T" | 12" W.Spruce N29E 72.0' "1/16S 8T" |
| 8" Sugar S64E 36.9' do | 6" B.Spruce N20W 49.20' do |
| 9" Sugar S54E 44.2' do | 10" W.Spruce N68W 33.45' do |
| 8" Balsam S02W 10.7' do | 6" W.Spruce S59W 45.35' do |
- Bearings are magnetic. Distances are to nail with tag. Set sq'd cedar post adjacent.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 5/19/04

For the Michigan Department of Natural Resources, Office of Land and Facilities