

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>45N</u> R <u>34W</u>	<u>F7</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

May 03 2004

Stephan J. Szyszkoski

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 20 \_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(F7) Quarter corner common to Sections 16 and 21. Established in 1851 by Guy Carleton midway and on line between Section corners 40.09 chains east and west. The position for the original corner fell in the Net River and was not monumented. Reestablished in 1974 by A.O.Enger midway and on line between Section corners E7 and G7 39.991 chains West and East. Mr. Enger placed witness monuments on the section line 1.830 chains east and 4.016 chains west of the reestablished position: 1"IDx36" I.pipe with 4" MDNR cap 1.830 ch easterly, W.Birch 16 S50E 9.9', B.Ash 7 N11E 19.7'. 1"IDx36" I.pipe with 4" MDNR cap 4.016 ch westerly, B.Ash 16 N23E 18.6', Elm 42 S13W 39.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F7) The position for the corner falls in the Net River. No monumentation was recovered at the corner position. Found the 1974 witness corners established by A.O.Enger, and found them to be in substantial accord with the 1974 record. For the purposes of subdividing Sections 16 and 21, I computed the position of F7 by single proportionate measurement to the 1974 record between the two witness corners. F7 is therefore on a straight line between the two witness corners, 120.62' westerly of the monument on the east side of the Net River and 264.71' easterly of the monument on the west side of the Net River. Accessories for the two witness corners are described below.

The witness corner monuments were both recovered at record bearing and distance from the 1974 accessories, the dead remains of all being present except that of the 42" Elm (at the westerly witness monument), which was not recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F7) Found witness corner monument on the West side of the Net River. 1"ID I.pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in:  
 6" Balsam N08E 24.7' "MC NBT"  
 14" W.Spruce N88W 49.5' do  
 10" W.Spruce N61W 40.5' do  
 7" B.Ash N17W 19.9' do  
 Bearings are magnetic. Distances are to nail with tag. Sq'd cedar post adjacent.

(F7) Found witness corner monument on the East side of the Net River. 1"ID I.pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in:  
 6" Maple N79E 34.3' "MC NBT"  
 13" Spruce S64E 33.9' do  
 5" B.Ash S22E 22.0' do  
 12" B.Ash N48W 9.6' do  
 Bearings are magnetic. Distances are to nail with tag. Sq'd cedar post adjacent.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 5/19/04

For the Michigan Department of Natural Resources, Office of Land and Facilities