

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>34W</u>	<u>C1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>9</u> T <u>45N</u> R <u>34W</u>	<u>5</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

5 Nov 07 2005
 C1 Nov 01 2005

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C1) Corner common to Sections 5 and 6 T45N-R34W and Sections 31 and 32 T46N-R34W. Remonumented and approved by the Iron County Peer Group in 1996, having been remonumented by Gary L. Pisoni PS27457 with a 2" dia. aluminum pipe monument with a 3" cast aluminum cap and the following witnesses: 12" W.Spruce N71E 12.01', 11" W.Spruce S50E 27.04', 11" W.Spruce S18W 28.14', 8" B.Spruce N77W 16.36', 6' Steel sign post N07E 1.03', Wood post N80E 35.00'. Corner record is filed in Liber 7 of LCR, Page 40.
 (5-Sec. 9) North 1/16 corner, Section 9. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C1) Recovered the 1996 monument, as described in the record, in good condition, and at record bearing and distance from the 1996 NBTs. The NBT W.Spruce N71E and B.Spruce N77W are now dead. Left the monument in place and made two new witnesses as described below.
 (5-Sec. 9) Established the corner midway and on a straight line between Quarter corner 1308.65' North and the Intersection of Quarter lines 1308.65' South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C1) Found 2" dia. alum. pipe with 3" cast alum. Iron County cap. Set measuring nails in:	(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
12" W.Spruce S80E 21.1' mrkd "S5 NBT"	9" Sugar N39E 23.5' mrkd "1/16S BT"
7" W.Spruce West 8.1' "S6 NBT"	8" Maple N66E 14.3' do
The 1996 NBTs / found nail in side	4" Sugar S09W 4.8' do
12" W.Spruce S19W 28.1' with scribing	6" Sugar N37W 14.9' do
12" W.Spruce S49E 27.0' overgrown blaze	Set sq'd cedar post adjacent. Bearings
Bearings are magnetic. Distances are to nail with tag. Fd. Steel sign post N07E 1.03'.	are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/19/06

For the Michigan Department of Natural Resources, Office of Land and Facilities