

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>34W</u>	<u>D2</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T <u>45N</u> R <u>34W</u>	<u>8</u>
	S <u>5</u> T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		●	●		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

May 07 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- (D2) Center of Section 5. Not established in the original survey. Found no subsequent record.
- (8-Sec. 5) West 1/16 corner, Section 5. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (D2) Established the corner at the intersection of a straight line connecting the North and South Quarter corners of Section 5 with a line passing through the Quarter corner common to Sections 5 and 6 and being parallel to the south line of Section 5 from corner C3 to corner E3.
- (8-Sec. 5) Established the corner midway and on a straight line between Quarter corner 1317.33' West and Center of Section 1317.33' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (D2) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in: | (8) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in: |
| 5" Tamarack N66E 13.4' mrkd "C1/4 BT" | 6" Sugar N77E 32.5' mrkd "1/16S BT" |
| 5" B.Spruce S38E 29.2' do | 9" Maple S26E 15.8' do |
| 7" Tamarack South 19.1' do | 11" Maple S08W 9.5' do |
| 4" B.Spruce S10W 9.5' do | 7" Maple S82W 28.7' do |
| Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. | Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/19/06

For the Michigan Department of Natural Resources, Office of Land and Facilities