

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>45N</u> R <u>34W</u>	<u>I4</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T <u>45N</u> R <u>34W</u>	<u>SNC north of #4</u>	
	S <u>2</u> T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

SMC May 16 2007
I4 May 30 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I4) Quarter corner common to Sections 10 and 11. 1851 - Established by Guy Carleton, Deputy Surveyor: Set quarter section post midway between Section corners 40.30 chains north and south. Y. Birch 16 N58E 30 links, Fir 10 S64W 26 links. 1965 - corner mentioned in LCRC Liber 2 Page 432 by Neal Spherhake RLS: "corner...is a wooden post. Names and dates on the trees show this post has been the accepted 1/4 corner between Sections 10 and 11 for a long period of time and cruise maps in the office of the Marathon Corporation show there was a bearing tree present in 1930". Mr. Spherhake used the post's position to reestablish corner 15, 39.995 chains south. (SMC north of #4) Special Meander Corner on the West N-S 1/16 line of Section 2, 1198.30' north of the NW1/16 corner (#4, Sec. 2). Corner not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I4) The original post and accessories were not recovered. Found the post noted by Mr. Spherhake, a rotting squared cedar post, now down and covered by leaf litter, with 3 location tags facing its position. The oldest tag, by Nothern Paper Mills, is undated but is affixed to a dead and down Balsam. Distance south to Section corner was found to be 2641.82', which agrees with Mr. Spherhake's distance of 2639.67'. Distance north to an iron pipe at I3 was found to be 2640.81'. The post is 26.45' East of a straight line between the Section corners. Accepted the post as the best available evidence of the position of the original corner and replaced it with a monument, as described below.
(SMC) Established the corner on the West N-S 1/16 line (mean bearing of N-S 1/4 line and West line of Section 2) 30' south of the water's edge of the "Wide Waters" of the Net River.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I4) Set 1"x32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 5" Sugar N44E 3.1' mrkd "1/4S NBT" 5" Sugar S19E 34.5' do 8" Sugar S85W 30.3' do 5" Sugar N34W 16.0' do Set sq'd spruce post adjacent. Bearings are magnetic. Distances are to nail with tag.	(SMC) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 3" Ash S28W 47.6' mrkd "SMC BT" 7" Ash S62W 54.1' do Distances are to nail with tag. Placed Sq'd cedar post N04W 0.9' Placed Sq'd cedar post S04E 1.0' Bearings are magnetic. Edge of water is 30' north and 25' east.
--	---



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 5/31/07

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													