

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 45N R 34W	G10
	T 45N R 34W	B11
2. Property Controlling in Section	T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on B11 10/12/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G10) Quarter corner common to Sections 27 and 28. 1965 - Neal Spherhake RLS reestablished the corner midway and on the Section line between Section corners 39.81 chains north and south. Set 1"ID x36" I.pipe with aluminum Kimberly-Clark Corp cap. Tamarack 6" N87E 21 links, Tamarack 6" S14W 18 links.

(B11) Quarter corner common to Sections 30 and 31. 2000 - Corner recorded by Gary L. Pisoni RLS for Iron County Remonumentation. Rec. Liber 8 of LCRC, Page 246. Found 1"ID Iron pipe with 4" aluminum Michigan Dept. of Natural Resources cap. 13" Spruce N21W 30.04', 9" Spruce S08W 23.56', 9" Poplar S31E 31.90', 11" Red Maple West 38.96', Steel sign post N45E 0.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G10) Found the 1965 monument in good condition and at record bearing and distance from the 1965 NBTs, both in good condition with overgrown double blazes. The position for the corner is in accord with the 1965 record and I accept the monument as a careful and faithful reestablishment of the position of the original corner.

(B11) Found the monument in good condition and at record bearing and distance from the 9" Spruce S08W and 11" Maple (fnd Sugar Maple) West NBTs, and Steel sign post. Left the monument in place and made new accessories as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G10) Fd. 1"ID I.pipe with 4" alum. Kimberly-Clark cap. Set meas. nail with MDNR tag in:
 9" Tamarack N86E 13.75' old blazes 1965 NBT
 9" Tamarack S17W 11.8' do do
 11" Tamarack N39E 22.1' mrkd "1/4S NBT"
 8" Y.Birch S65W 9.2' do
 Bearings are magnetic.

(B11) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Found nail and tag in the side of:
 8" Spruce S11W 23.6' overgrown blazes
 12" Sugar N87W 38.95' scribing visible.
 Set measuring nail with MDNR tag in the side of:
 8" Maple S18W 26.5' mrkd "1/4S NBT"
 5" Balsam N68W 23.8' do
 Steel sign post N47E 0.85'
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/03/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities