

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 45N R 34W	G11
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 28 T 45N R 34W	9
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 9 10/01/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G11) Corner common to Sections 27-28-33-34. 1851 - Established by Guy Carleton Deputy Surveyor. Set post. Tamarack 6" N64W 18 links, Tamarack 6" S40E 77 links. Northern Paper Mills record dated Oct. 10, 1953 shows: April 1931: B.G.Buell and Jacobson found orig. post and Tam. 6 N64W 18 as a stub I.M. plain. Dec.1946: Mitchell and Kuhumuench found orig. post and Tam. NW in fair shape. Found L.E.S. post and N.P.M.L.P. Oct. 1953: D.Buell & H.Gerry found Tam. S40E 77 stub. I.M. fair. Orig. post rotted off. Paint still there. L.E.S. post and NPMLP. Set pipe at orig. post. Spruce 8" S85E 116 links.

(9-Sec. 28) East 1/16 corner, Section 28. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G11) Found a 1"ID I.pipe capped with a 2" brass Northern Paper Mills cap, stamped to identify the corner, at record bearing and distance from the 1953 Spruce NBT SE, in good condition with scribing visible. Found 2.5" sq. white LES post North 1.4', 18" tall. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(9-Sec. 28) Established the corner midway and on a straight line between 1/4 corner 28/27 1324.44' east and the intersection of 1/4 lines of Section 28 1324.44' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G11) Fd. 1" I.pipe with 2" brass cap. Set measuring nail with MDNR tag in the side of:
 8" Spruce S80E 76.95' old marks 1953 NBT
 3" Spruce N48W 33.6' mrkd "S28 NBT"
 4" Spruce S80W 43.7' "S33 NBT"
 3" Tamarack South 56.1' "S34 NBT"
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" Sugar N22E 13.9' mrkd "1/16S BT"
 5" Sugar S55E 13.35' do
 12" Y.Birch S04W 16.0' do
 7" double Sugar S57W 24.3' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/02/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities