

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 29 T 45N R 34W	8
	S 29 T 45N R 34W	11
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/27/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(8-Sec. 29) West 1/16 corner, Section 29. Not established in the original survey.

(11-Sec. 29) Southwest 1/16 corner, Section 29. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8-Sec. 29) Established the corner midway and on a straight line between Quarter corner 1342.57' west and the intersection of 1/4 lines 1342.57' east.

(11-Sec. 29) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. For 1/16 corner #15, Section 29, I did not accept the position of the 1974 monumented corner of record. Instead, I used a point located midway and on the Section line between Section corner C11 and Quarter corner D11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 11" B.Ash N10E 16.4' mrkd "1/16S BT"
 6" B.Ash N78E 3.75' do
 7" B.Ash S05E 7.7' do
 5" Balsam S72W 19.4' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

(11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 5" W.Birch N45W 38.6' mrkd "1/16S BT"
 2" W.Birch S75E 10.7' do
 4" Balsam S25E 42.7' do
 3" Spruce S04W 30.95' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 08/17/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

