

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u>	<u>Located In:</u>	<u>Corner Code #</u>	
(County)			
1. Public Land Survey	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S <u>32</u> T <u>45N</u> R <u>34W</u>	<u>3</u>	_____
	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/28/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(3-Sec. 32) North 1/16 corner between Sections 31 and 32. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(3-Sec. 32) From the position for the corner, midway and on the Section line between Section corner 1319.95' north and Quarter corner 1319.95' south, I found a 5/8" rebar 0.10' west and 0.03' north. I accepted the rebar as a careful and faithful determination of the position of the corner and placed a plastic MDNR cap on it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(3) Fd. 5/8" rebar. Placed MDNR plastic cap atop.
 Set measuring nail with MDNR tag in the side of:
 7" W.Birch N15E 14.9' mrkd "1/16S BT"
 7" W.Birch S61E 3.0' do
 4" Maple S12E 20.0' do
 4" Balsam N43W 5.6' do
 "T" fence post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 08/13/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities