

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 45-46N R 31W

DESCRIPTION OF CORNER 1/4 corner between Sections 4 and 33

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 20, 1969

WITNESSES TO CORNER..... Sugar Maple 7 South 19 links "1/4S NBT"



Red Maple 6 N80°E 17 links "1/4S NBT"

Bearings are magnetic

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by proportionate measurement on line between section corners 39.92 chains to east and west. Found no evidence of original monument or its accessories. Found a squared and painted 1" picket, with Celotex Corp. location poster facing it, bearing N5E 72 links from corner as here re-established.

Variation is 0°07' East at this corner.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 2/24/70
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68