


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron COUNTY
T 45-46N R 31W

DESCRIPTION OF CORNER East 1/16 corner between Section 4 and 33
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED June 24, 1969
WITNESSES TO CORNER..... Sugar Maple 12 S90°E 52 links "1/16S BT"



Sugar Maple 15 N19½°E 16½ links "1/16S BT"
Bearings are magnetic
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by proportionate measurement on line between section corners 19.96 chains east and 59.88 chains west. Found no evidence that the corner had ever been established here previously, but found a picket marked "60.00 West" bearing N4°30' E 88½ links, on a yellow paint line.

Variation at this corner is 0°07' East.

SURVEYOR'S SEAL

DISTRIBUTION: SIGNED Arthur O. Enger DATE 2/19/70
REGISTERED LAND SURVEYOR

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing