

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY  
T 45-46N R 31W

DESCRIPTION OF CORNER West 1/16 corner between Sections 4 and 33

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 20, 1969

WITNESSES TO CORNER..... White Pine 6 N2°W 35½ links "1/16S BT"



White Spruce 8 S76°W 46 links "1/16S BT"

Bearings are magnetic

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by proportionate measurement on line between section corners 19.96 chains west and 59.88 chains east. Found no evidence that a corner was ever established here before.

Variation is 0°22' East.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Arthur O. Enger DATE 2/26/70  
REGISTERED LAND SURVEYOR

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68