

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Iron COUNTY
T 45-46N R 31W

DESCRIPTION OF CORNER 1/4 corner between Sections 3 and 34

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 6, 1969

WITNESSES TO CORNER..... Sugar Maple 9 S45 1/2°W 29 links "1/4 S NBT"



Sugar Maple 9 N63°W 31 1/2 links "1/4 S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by proportionate measurement on line between section corners 39.92 chains west and 119.75 chains east. Found no evidence or original monument or its accessories, but did find an old, partially squared, 10 inch cedar cruiser's tree (still green) bearing N62 1/2°E 32 links from corner as here re-established. Oldest legible name on this tree appears to be "Divine 6/12/50 (or 52)." Old east and west line blases pass just north of corner and a property line wire meanders east and west approximately along the section line. Original field notes call for "descend hill 15 feet course NW" 2.50 chains west of original quarter corner; this feature was found at about 2.25 west of corner as set here, but change is gradual and could be taken as anywhere between 2.00 and 2.50 chains.

Variation at this corner is 2°40' West.

SURVEYOR'S SEAL

SIGNED

Arthur D. Enger
REGISTERED LAND SURVEYOR

DATE

2/26/70

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68