

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T46N R 31W	M13	
	T46N R 31W	M11	
	T ___ R ___	_____	
2. Property Controlling in Section	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Mar 4, 2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 (M13) Corner to townships 45N-46N Ranges 30W-31W. 1961 - Reestablished by Neal Spermhake RLS. Set 1"IDx36" I.pipe with aluminum Kimberly-Clark Corp. cap. Balsam 4 N34W 42 links, Spruce 6 N45E 23.5 links, Tamarack 5 S51E 56 links.

(M11) Section corner common to Sections 25 and 36 T46N-R31W and Sections 30 and 31 T46N-R30W. 1961 - Neal Spermhake RLS reestablished the corner by single proportionate measurement to the original record. Set 1"IDx36" I.pipe with aluminum Kimberly-Clark Corp cap. W.Pine 16 N22W 19 links, Maple 4 N22E 47.5 links, Elm 5 S64E 27 links, Maple 7 S22W 76.5 links. 1986 - 1961 monument was recovered and accepted by K.L.Sackett RLS. Mr. Sackett noted that the 1961 witnesses were still in place and at record bearing and distance.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (M13) Recovered the 1961 monument in good condition and at record bearing and distance from the 1961 witnesses. The Spruce and Tamarack are in good condition, the Balsam is a dead stub with scribing visible. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

(M11) Found the 1961 monument in good condition and at record bearing and distance from the remaining 3 1961 NBTs: W.Pine in good condition, Maple NE in good condition, and Maple SW in good condition. The Elm NBT is dead and down and not visible under the snow. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 (M13) Found 1"ID I.pipe with alum. Kimberly-Clark Corp. cap. Set measuring nail with MDNR tag in the side of the following trees:  
 8" B.Spruce N43E 15.2' scribing vis. 1961 NBT  
 8" Tamarack S53E 37.0' overgrown blzs do  
 10" Cedar N88E 40.3' mrkd "S31 NBT"  
 5" B.Spruce N46W 21.5' "S36 NBT"  
 Sq'd Cedar post adjacent. Bearings magnetic.  
 (M11) Found 1"ID I.pipe with alum. Kimberly-Clark Corp. cap. Found measuring nail with tag by G.VanNeste RLS in the side of the following 5 trees:  
 19" W.Pine N24W 12.3' old blazes  
 10" Maple clump N37E 13.4' upper blaze  
 9" Maple clump S41E 12.6' do  
 8" Sugar S18W 27.7' do  
 12" W.Spruce S69W 19.4' do  
 12" Maple N19E 31.4' Set MDNR tag/nail  
 12" Maple S22W 50.8' do  
 Bearings magnetic.

Signed by Stephan J. Szyszkoski



Date 3/5/08

Surveyor's Michigan License No. 33986