

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>31W</u>	<u>K9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	S <u>25</u> T <u>46N</u> R <u>31W</u>	<u>1</u>
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Feb 28, 2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (K9) Corner common to Sections 23-24-25-26. 1986 - Remonumented by K.L.Sackett RLS at position of old post. Set 1"IDx36" I.pipe with plastic cap # 19006. 10" Balsam S14W 6.6', 5" Maple N79E 11.8', 5" Maple S13E 28.2'.

(1-Sec. 25) West 1/16 between Sections 24 and 25. 1986 - Monumented by K.L.Sackett RLS midway and on line between Section and Quarter corners. Set 1"IDx36" I.pipe with plastic cap # 19006. 4" Maple S68W 6.6', 8" Sugar S64E 30.2', 3" Maple N48E 28.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (K9) Found the 1986 monument in good condition and at record bearing and distance from the 1986 witnesses. The Maple witnesses are in good condition. The Balsam is standing dead. Accepted the monument as the best available evidence of the position of the original corner.

(1-Sec. 25) Found but did not accept the 1986 monument of record. The monument was found to have been installed S46W 39.4' from the position described in the 1986 record. Reestablished the corner midway and on the Section line between Section corner 1320.24' west and Quarter corner 1320.24' east. Removed the 1986 monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (K9) Found 1"ID I.pipe with plastic cap # 19006. Set measuring nail with MDNR tag in the side of:
 8" Maple N80E 12.1' scribing visible (1986 wit.)
 8" Maple S11E 28.7' do do
 4" Spruce North 11.0' mrkd "S23 NBT"
 6" Sugar S87W 14.9' "S26 NBT"
 4x4 treated post adjacent. Bearings magnetic.
 (1-Sec. 25) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Sugar N21E 33.0' mrkd "1/16S BT"
 5" Sugar N65E 12.9' do
 10" Sugar S06W 46.9' do (old 1986 wit)
 7" Sugar S51W 45.4' do
 Sq'd cedar post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski



3/5/08

Surveyor's Michigan License No. 33986