

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>25</u> T <u>46N</u> R <u>31W</u>	<u>8</u>
3. Miscellaneous Property in Sec.	S <u>25</u> T <u>46N</u> R <u>31W</u>	<u>4</u>
	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

**Register of Deeds Stamp & File Number**

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on Mar 3, 2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(8-Sec. 25) West 1/16 corner, Section 25. Not established in the original survey.

(4-Sec. 25) Northwest 1/16 corner, Section 25. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(8-Sec. 25) Established the corner midway and on a straight line between Quarter corner 1318.92' west and Center of Section 1318.92' east.

(4-Sec. 25) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 5" Spruce N21W 31.9' mrkd "1/16S BT"  
 12" Spruce N86E 43.3' do  
 3" Spruce S16E 17.8' do  
 6" Spruce S89W 6.3' do  
 Sq'd cedar post adjacent. Bearings magnetic.  
 Sq'd a 3" Spruce S80E 2.2'.

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 4" Spruce N13E 11.3' mrkd "1/16S BT"  
 9" Spruce N60E 29.9' do  
 5" Spruce S37E 23.3' do  
 6" Spruce S51W 13.4' do  
 Sq'd a 3" Balsam S14E 1.4' for a post.  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski



Date 3/5/08

Surveyor's Michigan License No. 33986