

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Iron</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S <u>36</u> T <u>46N</u> R <u>31W</u>	<u>7</u>
2. Property Controlling in Section	S <u>25</u> T <u>46N</u> R <u>31W</u>	<u>14</u>
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**Register of Deeds Stamp & File  
Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on Mar 4, 2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 (7-Sec. 36) North 1/16 corner between Section 36 T46N-R31W and Section 31 T46N-R30W. Not established in the original survey.  
 (14-Sec. 25) South 1/16 corner between Section 25 T46N-R31W and Section 30 T46N-R30W. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (7-Sec. 36) Established the corner midway and on the Range line between Section corner 1323.41' north and Quarter corner 1323.41' south.  
 (14-Sec. 25) Established the corner midway and on the Range line between Section corner 1313.67' south and Quarter corner 1313.67' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 (7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 3" B.Spruce S37E 44.1' mrkd "1/16S BT"  
 4" B.Spruce S15E 32.2' do  
 8" Tamarack S06W 41.6' do  
 6" Balsam S71W 49.7' do  
 Sq'd cedar post adjacent. Bearings magnetic.  
 (14) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 7" B.Spruce N32E 6.2' mrkd "1/16S BT"  
 4" Tamarack S71E 5.9' do  
 5" Tamarack S23W 9.8' do  
 7" B.Spruce N76W 9.9' do  
 Sq'd cedar post adjacent. Bearings magnetic.



Signed by Stephan J. Szyszkoski

Date 3/5/08

Surveyor's Michigan License No. 33986