

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T 46N R 31W	L13
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 36 T 46N R 31W	12
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on L13 05/27/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L13) Quarter corner common to Section 36 T46N-R31W and Section 1 T45N-R31W. 1846 - Established by Wm.A.Burt midway and on the Township line between Township corner 40.00 chains east and Section corner 40.00 chains west. Set post. Spruce 8" N15E 21 links, Spruce 6" N19W 5 links.

(12-Sec. 36) South 1/16 corner, Section 36. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L13) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner on the Township line, midway between Section corner 2616.30' west and Township corner 2616.30' east.

(12-Sec. 36) Established the corner midway and on a straight line between Quarter corner 1308.37' south and Center of Section 1308.37' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>(L13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 4" B.Spruce N68E 10.0' mrkd "1/4S NBT" 24" W.Pine S59E 28.8' do 5" B.Spruce S03E (no dist.) do 11" W.Pine N43W 2.8' do Sq'd cedar post N68E 1.0' (no tag) Bearings are magnetic.</p>	<p>(12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 5" Maple N31E 26.3' mrkd "1/16S BT" 6" Maple N71E 42.4' do 6" Maple S08E 24.2' do 7" Balsam S61W 9.3' do Set sq'd post adjacent. Bearings magnetic.</p>
--	---

Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 06/24/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities