

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 36 T 46N R 31W _____	L12
	S 36 T 46N R 31W _____	10
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2			1	
3													
4	7		8		9		10		11			12	
5													
6	18		17		16		15		14			13	
7													
8	19		20		21		22		23			24	
9													
10	30		29		28		27		26			25	
11													
12	31		32		33		34		35				
13													

I, Stephan J. Szyszkoski, in a field survey on L 12 05/27/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(L12) Center of Section 36. Not established in the original survey.

(10-Sec. 36) South 1/16 corner between Sections 35 and 36. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(L12) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(10-Sec. 36) Established the corner midway and on the Section line between Quarter corner 1315.77' north and Section corner 1315.77' south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(L12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 5" Poplar N15E 71.1' mrkd "C1/4 BT"  
 3" W.Spruce N52E 43.5' do  
 4" Poplar N87E 57.0' do  
 3" W.Spruce S39E 48.3' do  
 Set sq'd post adjacent. Bearings magnetic.

(10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 4" Balsam N58E 52.45' mrkd "1/16S BT"  
 3" Sugar EAST 15.8' do  
 5" Sugar S03W 23.2' do  
 14" Spruce N87W 6.15' do  
 Set sq'd post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski Date 06/24/2008  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities



16078  
16079