

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 46N R 31W	K12
	T 46N R 31W	K13
2. Property Controlling in Section	S _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on K12 05/22/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K12) Quarter corner common to Sections 35 and 36. 1848 - Established by Harvey Mellen, Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains north and south. Set Y.Birch post. W.Pine 12" S73W 98 links, Y.Birch 6" S9W 31 links.

(K13) Corner common to Sections 35-36 T46N-R31W and Sections 1-2 T45N-R31W. 1969 - Remonumented by A.O.Enger RLS at the site of an old squared pine post and mound of rocks. Set 1"IDx36" iron pipe with 4" aluminum cap. B.Spruce 8" N50W 17.5 links, B.Spruce 12" N70E 20.5 links, Red Maple 5 S52E 24.5 links, W.Pine 5" S4W 50.5 links. Record filed in 1971.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K12) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2631.54' north and south.

(K13) Recovered the 1969 monument in good condition and at record bearing and distance from the rotted stump remains of the 1969 NBTs B.Spruce N70E and R.Maple S52E. The other two NBTs were not found and are presumed lost to logging activity. Accepted the monument as the best available evidence of the position of the original corner and made new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 5" Spruce N80E 34.2' mrkd "1/4S NBT"
 5" Maple S70E 15.35' do
 6" double Maple S65W 34.75' do
 5" Poplar S72W 6.8' do
 Set sq'd post adjacent. Bearings are magnetic.

(K13) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 5" Spruce N67E 39.6' mrkd "S36 NBT"
 7" Maple N85E 44.8' do
 5" Spruce S67E 24.7' "S1 NBT"
 5" Balsam S57W 7.2' "S2 NBT"
 Set sq'd post adjacent. Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 06/24/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities



16074
16075