

LAND CORNER RECORDATION CERTIFICATE

Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Stephan J. Szyszkoski

Field Survey Date: September 7, 2016

For corner(s) in: Iron County

Original Public Land Survey Corner		Corner Code
S _____	T <u>46N</u> R <u>32W</u>	<u>F09 (GCDB 340300)</u>
S _____	T _____ R _____	_____
S _____	T _____ R _____	_____
S _____	T _____ R _____	_____
Property Corner		1/16 Corner Code
S _____	T _____ R _____	_____
S _____	T _____ R _____	_____
S _____	T _____ R _____	_____
S _____	T _____ R _____	_____

1	A	B	C	D	E	F	G	H	I	J	K	L	M	1
2		6		5		4		3		2		1		2
3														3
4		7		8		9		10		11		12		4
5														5
6		18		17		16		15		14		13		6
7														7
8		19		20		21		22		23		24		8
9						●								9
10		30		29		28		27		26		25		10
11														11
12		31		32		33		34		35		36		12
13	A	B	C	D	E	F	G	H	I	J	K	L	M	13

Part A. Corner History

Quarter corner common to Sections 21 and 28. 1852 - Established by Francis Houck, U.S. Deputy, midway and on the Section line between Section corners 39.68 chains east and west. Set post. W.Pine 24" N32°E 9 links, Spruce 12" S29°W 23 links. Found no subsequent record.

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner midway and on the Section line between Section corners 2617.36' east and west, proportionate to the original record.

Part C: Field Evidence of Perpetuation or Monumentation of Corner

Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 5" Poplar N43°E 18.3' mrkd "1/4S NBT"
 5" Sugar N88°E 33.1' do
 11" Maple S12°W 21.5' do
 10" Maple S66°W 14.3' do
 Set sq'd cedar post adjacent.
 E= 7898804.202 N= 176323.217

Bearings are magnetic. Coordinates are MCS83, NAD83(2011) Epoch 2010.00, in meters.
 Coordinate Reference: MDNR Network control "BONE", a 1"ID I.pipe with 2" alum cap., E= 7899059.778 m. N= 176329.657 m.

Stephan J. Szyszkoski 10/13/2016

