

**LAND CORNER RECORDATION CERTIFICATE**  
**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**

Iron County FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 46 N. R. 33 E.	G9, F9
2. PROPERTY CONTROLLING IN SECTION 28 _____	T. 46 N. R. 33 E.	2, 1
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER \_\_\_\_\_

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-13-85, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner G9: Original monument and accessories not found. Found Northern Paper Mill's monument set by Bruce Buell.  
 Corner 2: Not set on original survey nor subsequently apparently.  
 Corner 1: Not set on original survey nor subsequently apparently.  
 Corner F9: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner G9: Restored at monument.  
 Corner 2: Established midway and on line between corners east and west.  
 Corner 1: Established midway and on line between corners east and west.  
 Corner F9: Restored midway and on line between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G9: Northern Paper Mills Monument	Corner 1: Set 1" ID X 32" IP w/4" alum. cap.
10" sugar N85W 6.9' S21, NBT	3" spruce S45E 21.6' 1/16S, BT
7" sugar N10E 17.2' S22, NBT	3" spruce S25W 28.3' 1/16S, BT
5" sugar S16E 22.7' S27, NBT	
Corner 2: Set 1" ID X 32" IP w/4" alum. cap.	Corner F9: Set 1" ID X 32" IP w/4" alum cap.
7" maple N50E 15.7' 1/16S, BT	7" maple S46E 33.5' 1/4S, NBT
10" maple N72W 44.0' 1/16S, BT	4" poplar S58W 8.7' 1/4S, NBT
8" maple S30W 50.7' 1/16S, BT	6" poplar N40W 10.0' 1/4S, NBT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Michael Rose CHIEF OF SURVEY PARTY DATE 5-14-85

APPROVED AND SIGNED BY Keith L. Sackett DATE 5-19-85

MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett  
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006