

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

| Iron County FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|--|---------------------------------|--------------------|
| 1. PUBLIC LAND SURVEY..... | T. <u>46</u> N. R. <u>33</u> W. | <u>D9, C7</u> |
| 2. PROPERTY CONTROLLING IN SECTION <u>29</u> | T. <u>46</u> N. R. <u>33</u> W. | <u>1, 2</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION..... | T. _____ N. R. _____ W. | _____ |
| 4. LOT NO. _____, RECORDED PLAT..... | | |
| 5. PRIVATE CLAIMS..... | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-13-85, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 Corner D9: Original monument and accessories not found.
 Corner 1: Not set on original survey nor subsequently apparently.
 Corner 2: Not set on original survey nor subsequently apparently.
 Corner C7: Original monument and accessories not found. Found 1½ iron pipe recorded by highway department.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Corner D9: Restored midway and on line between corners east and west.
 Corner 1: Established midway and on line between corners east and west.
 Corner 2: Established midway and on line between corners east and west.
 Corner C7: Restored at 1½ iron pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner D9: Set 1" ID X 32" IP w/4" alum. cap. 14" spruce N76W 7.3' ¼S, NBT
 9" spruce S38W 20.2' ¼S, NBT
 Corner 1: Set 1" ID X 32" IP w/4" alum. cap. 18" Cedar S01E 15.5' 1/16S, BT
 14" Cedar S34W 20.0' 1/16S, BT
 12" Spruce N06E 12.2' 1/16S, BT
 Corner 2: Set 1" ID X 32" IP w/4" alum. cap. 5" spruce S54W 15.9' 1/16S, BT
 12" spruce S08E 58.1' 1/16S, BT
 Old Fence corner north 14 feet.
 Corner C7: 1½ ID Iron Pipe 6" maple S01E 9.0' S20, NBT
 5" sugar N45W 8.2' S18, NBT
 4" maple N30E 7.4' S17, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (REAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Michael Stone DATE 5-14-85
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY Keith L. Sackett DATE 5-14-85
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006