

**LAND CORNER RECORDATION CERTIFICATE**  
**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**

Iron County

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>46</u> N. <u>33</u> W. <u>IX</u>		<u>B11, B9, A9, A10</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. _____ E. _____ S. _____ R. _____ W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. _____ E. _____ S. _____ R. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-2-85, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law.

A. Description of original monument and accessories and/or subsequent restoration:  
 Corner B11: Original monument and accessories not found.  
 Corner B9: Original monument and accessories not found.  
 Corner A9: Original monument and accessories not found. Found old cedar post.  
 Corner A10: Original monument and accessories not found. Found possible original bearing tree but no positive marks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 Corner B11: Restored on line between section corners east and west.  
 Corner B9: Restored by proportion on line between section corners east and west.  
 Corner A9: Restored at old cedar post, has been used as corner for many years.  
 Corner A10: Restored midway and on line between section corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.  
 Corner B11: 1" ID X 28" IP with 4" alum. cap. 14" sugar S80W 3.6'  
 12" sugar N52E 13.55' Masonary nail and ref. tag in lower blaze.  
 8" sugar S72E 17.45' Nail and ref. tag in side.  
 Corner B9: 1" ID X 32" IP with 4" alum. cap. 5" sugar S18E 13.0' 1/4S, NBT  
 6" sugar N64E 19.0' 1/4S, NBT  
 5" maple N12W 11.4' 1/4S, NBT  
 5" maple squared south 1'  
 Corner A9: 1" ID X 32" IP with 4" alum. cap. 8" sugar S34E 17.7' S30, NBT  
 6" sugar S42W 8.9' S25, NBT  
 7" maple N54W 5.5' S24, NBT  
 Corner A10: 1" ID X 32" IP with 4" alum. cap. 12" sugar S60W 58.1' 1/4S, NBT  
 4" sugar N38W 22.9' 1/4S, NBT  
 Northern Paper Mills location poster on 10" poplar S70E 14.0' dates to 1945.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (REAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Michael Siro DATE 5-14-85

APPROVED AND SIGNED BY Keith L. Sackett DATE 5-10-85

MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett  
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
 REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET