

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR COUNTY OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 33 W.	E10, E11
2. PROPERTY CONTROLLING IN SECTION	28 T. 46 N. R. 33 W.	3
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-23-85, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 Corner E10: Original monument and accessories not found.
 Corner E11: Original monument and accessories not found. Found two old posts set in open marsh.
 Corner 3: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Corner E10: Restored midway and on line between corners north and south.
 Corner E11: Restored at old post. This is the area of original corner. This post has been used as corner for many years.
 Corner 3: Established midway and on line between corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner E10: Set 1" I.D. by 32" I.P. w/4"/alum. cap.
 4" spruce S40E 16.2' 1/4S, NBT
 10" spruce N39E 6.7' 1/4S, NBT
 10" spruce N62W 17.3' 1/4S, NBT
 Corner E11: Set 1" I.D. by 36" I.P. w/4"/alum. cap.
 Placed 6" post painted blue in open marsh.
 No available NBT's.
 Corner 3: Set 1" I.D. by 36" I.P. w/4"/alum. cap.
 4" spruce S61W 9.9' 1/16S, BT
 4" spruce S55E 5.3' 1/16S, BT
 4" spruce N27E 13.7' 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 5.30.85

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Department of Natural Resources

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006