

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Iron County FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 33 E.	E9, C8
2. PROPERTY CONTROLLING IN SECTION 32	T. 46 N. R. 33 E.	3
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-13-85, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 Corner E9: Original monument and accessories not found. Found Highway Dept. bearing trees in poor shape.
 Corner C8: Original monument and accessories not found.
 Corner 3: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Corner E9: Restored from Highway Dep. BT's.
 Corner C8: Restored midway and on line between corners north and south.
 Corner 3: Established midway and on line between section corners north and position for 1/4 corner south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner E9: Set 1" ID X 32" IP w/4" alum. cap. 6" spruce S15W 5.0' S29, NBT
 5" spruce N50W 21.8' S20, NBT
 3" spruce N30E 8.4' S21, NBT
 Corner C8: Set 1" ID X 32" IP w/4" alum. cap. 6" spruce N82E 6.3' 1/4S, NBT
 5" maple S71W 3.0' 1/4S, NBT
 4" maple N28W 19.7' 1/4S, NBT
 Corner 3: Set 1" ID X 32" IP w/4" alum. cap. 9" sugar N08W 4.1' 1/16S, BT
 8" sugar S80W 18.7' 1/16S, BT
 8" sugar S70E 26.1' 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Michael Rose DATE 5-14-85
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY Keith L. Sackett DATE 5-14-85
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006