

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(IRON COUNTY)

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|-------------------------------------------|-------------------------------------------------------|--------------------|
| 1. PUBLIC LAND SURVEY_____ | T. <u>46</u> N. <u>33</u> XX W. | C-9 & C-11 |
| 2. PROPERTY CONTROLLING IN SECTION_____ | T. _____ N. _____ S. _____ R. _____ E. _____ W. _____ | _____ |
| 3. MISCELLANEOUS PROPERTY IN SECTION_____ | T. _____ N. _____ S. _____ R. _____ E. _____ W. _____ | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner C9 (Section Corner 19, 20, 29, & 30, T46N, R33W):**
 Wood post (Possibly found. See B for subsequent monument.)
 W. Pine 36 S44E 36 (Found. NBT: Sugar Maple 24 S77°W 29.1 ft. "S30, NBT"
 Sugar 12 N30W 38 (" " : Y. Birch stub 16 N61°E 26.0 ft. "S20, NBT"
- Corner C11 (Section Corner 29, 30, 31, & 32, T46N, R33W):**
 Wood post (Not found. See B for subsequent monument.)
 Y. Birch 12 N55E 45 (" " . NBT: Hemlock* 18 N40°E 28.1 ft. "S29, NBT"
 Cedar 12 S51W 2 (" " . " : Red Maple 11 S58°W 16.9 ft. "S31, NBT"
- *Windthrown, leaning, probably doomed.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner C9:** On 9/9/77, replaced a 1" I.D. x 36" iron pipe with 2" brass cap set by Northern Paper Mills personnel on 3/5/53 from the original BT's. Also found point of rotted off very old post (possibly original) and a 3½' length of bent 3/4" I.D. Iron pipe. W. Pine BT stump still in place, no marks visible, and maple BT is still alive, with blazes overgrown. See NPM corner records for additional information.
- Corner C11:** On 9/20/77, replaced a 1" I.D. x 36" iron pipe with 2" brass cap set by Northern Paper Mills personnel in 1953 at site of an older wood post set from one of the original BT's in 1933, when the BT was last reported seen. No visible evidence of either BT on this date.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner C9:** 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
 Sugar Maple 5 N65°E (mag.) 13.1 ft. "S20, NBT"
 Sugar Maple 7 S45°E (mag.) 34.2 ft. "S29, NBT"

Declination is 3°30' West.

- Corner C11:** 1" I. D. x 36" iron pipe with 3 3/4" aluminum cap
 Red Maple 11 S63°E (mag.) 22.6 ft. "S32, NBT"
 Red Maple 7 N13°W (mag.) 15.7 ft. "S30, NBT"
 Declination is 3°20' East

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE May 25, 1978
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

