

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 46N R 33W	J1
	T 46N R 33W	I1
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1									●	●			
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on J1 08/12/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J1) Quarter corner common to Section 35 T47N-R33W and Section 2 T46N-R33W. 1846 - Established by Austin Burt Deputy Surveyor. Set Spruce post. Spruce 7" N33E 10 links, Tamarack 6" N40W 28 links. Found no subsequent record.

(I1) Corner common to Sections 34-35 T47N-R33W and 2-3 T46N-R33W. 1846 - Established by Austin Burt Deputy Surveyor. Set Fir post. Y.Birch 8" N57E 60 links, Y.Birch 10" N43W 32 links. 1852 - Francis Houck Deputy Surveyor marked Fir 10" S20W 26 links, Fir -- S51E 49 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J1) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner on the curved Township line and by single proportionate measurement to the original record between Section corner 2635.59' east and Township corner 23603.70' west.

(I1) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner on the curved Township line and by single proportionate measurement to the original record between Section corner 5271.19' east and Township corner 20968.11' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. The mon. leans a little to the east due to rock. The center of the cap marks the corner position. Set measuring nail with MDNR tag in the side of:
 5" Maple N45E 14.0' mrkd "1/4S NBT"
 8" Spruce S29E 12.2' do
 4" Maple S20W 20.0' do
 14" W.Pine S78W 18.4' do
 Set sq'd cedar post near. Bearings magnetic.

(I1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 5" Balsam N05E 20.65' mrkd "S35 NBT"
 2" Balsam N40E 6.1' do
 5" Balsam N87E 12.15' do
 3" Cherry S71E 6.65' "S2 NBT"
 Set sq'd cedar post near. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/06/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

