

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 46N R 33W	H1
	T 46N R 33W	G1
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on H1 08/17/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H1) Quarter corner common to Section 34 T47N-R33W and Section 3 T46N-R33W. 1846 - Established by Austin Burt Deputy Surveyor. Set Spruce post. Spruce 8" N55E 47 links, Fir 6" N22W 45 links. Found no subsequent record.

(G1) Corner common to Sections 33-34 T47N-R33W and Sections 3-4 T46N-R33W. 1846 - Established by Austin Burt Deputy Surveyor. Set Maple post. Maple 8" N35E 25 links, Y.Birch 12" N55W 26 links. 1852 - Francis Houck Deputy Surveyor marked Fir 12" S12W 29 links, Spruce 12" S64E 37 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H1) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner on the curved Township line and by single proportionate measurement to the original record between Section corner 7906.78' east and Township corner 18332.52' west.

(G1) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner on the curved Township line and by single proportionate measurement to the original record between Section corner 10542.37' east and Township corner 15696.92' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 16" Tamarack S55W 43.65' mrkd "1/4S NBT"
 3" Balsam N47W 15.75' do
 5" Balsam N04W 46.3' do
 4" Balsam N17E 54.1' do
 Set sq'd cedar post near. Bearings magnetic.

(G1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap made firm in a mound of rock. Set measuring nail with MDNR tag in the side of:
 6" twin Maple N13E 22.1' mrkd "S34 NBT"
 7" Balsam S82E 12.7' "S3 NBT"
 10" Maple S30W 21.35' "S4 NBT"
 5" Maple S66W 30.35' "S4 NBT"
 Set sq'd cedar post near. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/06/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities