

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Iron	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 46N R 33W	D1
	T 46N R 33W	C1
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on D1 08/19/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(D1) Quarter corner common to Section 32 T47N-R33W and Section 5 T46N-R33W. 1846 - Established by Austin Burt Deputy Surveyor. Set Cedar post. Fir 10" N48E 11 links, Fir 7" N31W 28 links. Found no subsequent record.

(C1) Corner common to Sections 31-32 T47N-R33W and 5-6 T46N-R33W. 1846 - Established by Austin Burt Deputy Surveyor. Set Cedar post. Y.Birch 16" N23E 28 links, Y.Birch 16" N29W 38 links. 1852 - Francis Houck Deputy Surveyor marked Y.Birch 16" S27E 39 links, Y.Birch 16" S32W 57 links. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(D1) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner on the curved Township line and by single proportionate measurement to the original record between Section corner 18449.15' east and Township corner 7790.15' west.

(C1) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner on the curved Township line and by single proportionate measurement to the original record between Section corner 21084.74' east and Township corner 5154.56' west.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(D1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 4" Tamarack N33W 10.25' mrkd "1/4S NBT"  
 2" Balsam S70E 8.2' do  
 6" Maple S13W 25.3' do  
 3" Tamarack West 8.35' do  
 Set sq'd cedar post near. Bearings magnetic.

(C1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 6" Sugar N29E 9.1' mrkd "S32 NBT"  
 8" Y.Birch S42E 13.5' "S5 NBT"  
 6" Sugar S60W 20.6' "S6 NBT"  
 6" Y.Birch N48W 20.4' "S31 NBT"  
 Set sq'd cedar post near. Bearings magnetic.

Signed by Stephan J. Szyszkoski Date 10/06/2009  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

