

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Iron _____ (County)	Located in:	Corner Code #
1. Public Land Survey	T16N R 34W	15
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Aug 06 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5								●				
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
(15) Corner common to Sections 10-11-14-15. Established in 1852 by Zelotes B. Searles: "S6'E Corrected... 80.00 Set post Cor. of Secs. 10,11,14,15. Y. Birch 4 S34W 15, Fir 8 N10E 7." Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(15) Re-monumented the corner at the probable original location determined by the recovery of an old post point, preserved below and rotted off at the water table, about 12' below the ground surface. The post was found at record bearing and distance from the root remains of an unidentified hardwood tree S38W 9.9' and from the root remains of an unidentified coniferous tree N13E 4.6', which I believe are the remains of the original bearing trees. A second, newer post point was found adjacent to the old point. It projects about 3' above ground. A cedar with approx 40 yr. old blazes facing the post point is also nearby. At the position of the older post I place a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(15) Set 1" pipe with 4" MDNR cap.
Blazed and scribed the following:
12" Cedar S62W 19.3' "S15 NBT"
12" Cedar N02W 111.9' "S10 NBT"
12" Cedar S47E 95.25' "S14 NBT"
9" Cedar S09W 53.1' "S15 NBT"
The 9" cedar leans heavily toward the monument. Placed a squared 9.5' long cedar post adjacent. Bearings are magnetic. Distances are to meas. notch.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 12/29/98

For the Michigan Department of Natural Resources - Forest Management Division